

INDEPENDENCE 307

MAST

- Hydraulically Raised
- Integrated Top Drive Torque Track
- 142' Height
- 750,000 lbs. Static Hook

SUBSTRUCTURE

- Lee C Moore Slot Box
- 30' Floor Height (RKB)
- 26'-11" Clear Height (RBC)
- 37'-1/2" Rotary Table
- Setback Capacity: 750,000 lbs.
- Racking Capacity: 29,484' (5.5" DP)

WALKING SYSTEM

- Hydraulic, Remote Controlled Stompers
- 200' Max (X)*
- 10' Max (Y)
- Integrated Cable Management System
- Custom Engineered Flowline

DRAWWORKS

- 1,500 HP Dual Speed - Alta®
- (1) 1,500 HP AC Motor

TRAVELING BLOCK ASSEMBLY

- 500 Ton Canrig® 1,250 AC Top Drive
- 51,400 ft.-lbs. Torque @ 118 RPM
- 500 Ton Traveling Block

PIPE HANDLING EQUIPMENT

- Forum® FR120 Iron Roughneck
- Forum® Pipe Wrangler

ENGINE PACKAGE

- (4) Cummins® QSK50 Diesel Engines
- (4) 1750 kVa Generator Sets
- Bi-Fuel Equipped

CONTROL SYSTEM

- Precise® VFD House
- Drillers Cabin w/Precise® Cyber Chair
- VFD Interlock relay for High Line Capability

MUD PUMPS

- (3) 1,600 HP Triplex - 7,500 PSI
- (3) 1,500 HP AC Motor

MUD SYSTEM

- 1000 BBL. Pit Capacity - 7,500 PSI
- (3) Derrick® Hyperpool Shakers
- Vacuum Degasser
- Desander
- Desilter
- MGS 1,200 GPM 72" D / 20' L

MUD MIXING EQUIPMENT

- (3) Chemical Mixing Hoppers
- Caustic Barrel

LIQUID STORAGE

- 375 BBL. Water Storage Tank
- 375 BBL. Diesel Storage Tank

BOP EQUIPMENT

- Trolley Beam Handling System
- (2) Hydraulic Winches
- 13-5/8" x 5,000 PSI, Annular
- 13-5/8" x 10,000 PSI, Single Ram
- 13-5/8" x 10,000 PSI, Double Ram
- 2-1/16" x 4-1/16" 10,000 PSI Choke Manifold
- (1) 7 Station Accumulator Skid

NDS® OFFERINGS

- ROCKit (Oscillator)
- REVit Z Torque (Stickslip Mitigation)
- SmartDRILL (Automated Connection Sequencing)
- SmartNAV (Directional Guidance)
- SmartPLAN (Drilling Roadmap)
- SmartSLIDE (Automated Directional)

SLB® OFFERINGS

- DrillSync PSDO (Oscillator)
- DrillSync RADS (Stickslip Mitigation)
- DrillSync Downlinking (Automated)
- DrillSync LDSS (Engine Management)
- DrillOps (ROP Optimizer)

TUBULARS

- Available at Operator's Request



INDEPENDENCE
CONTRACT DRILLING