INDEPENDENCE 322

MAST
- Hydraulically Raised
- Integrated Top Drive Torque Track
- 142’ Height
- 750,000 lbs. Static Hook

SUBSTRUCTURE
- Hydraulically Raised NOV® Ideal
- 25’ Floor Height (RKB)
- 22’-6” Clear Height (RBC)
- 37-1/2” Rotary Table
- Setback Capacity: 650,000 lbs.
- Racking Capacity: 25,000’ (5.5” DP)

WALKING SYSTEM
- Hydraulic, Remote-Controlled Stompers
- 200’ Max (X)*
- 35’ Max (Y)
- Integrated Cable Management System
- Custom Engineered Flowline

DRAWWORKS
- 2,000 HP Dual Speed - NOV®
- (1) 2,000 HP AC Motor

TRAVELING BLOCK ASSEMBLY
- 500 Ton NOV® TDS-11SH AC Top Drive
- 51,000 ft-lbs. Torque @ 110 RPM
- 500 Ton Traveling Block

PIPE HANDLING EQUIPMENT
- Forum® FR120 Iron Roughneck
- Canrig® Hydraulic Catwalk

ENGINE PACKAGE
- (4) CAT® 3512C Diesel Engines
- (4) 1750 kVa Generator Sets
- Bi-Fuel Equipped

CONTROL SYSTEM
- NOV® Amphion Drive House
- Drillers Cabin w/NOV® Amphion Chair

MUD PUMPS
- (3) 1,600 HP Triplex - 7,500 PSI
- DC Pumps w/ NOV® SCR Controls

MUD SYSTEM
- 1000 BBL. Pit Capacity - 7,500 PSI
- (3) Derrick® Hyperpool Shakers
- Vacuum Degasser
- MGS 600 GPM 48” D / 14’-10” L

MUD MIXING EQUIPMENT
- (2) Chemical Mixing Hoppers
- Caustic Barrel

LIQUID STORAGE
- 500 BBL. Water Storage Tank
- 500 BBL. Diesel Storage Tank

BOP EQUIPMENT
- Trolly Beam Handling System
- (2) Hydraulic Winches
- 13-5/8” x 5,000 PSI, Annular
- 13-5/8” x 10,000 PSI, Single Ram
- 13-5/8” x 10,000 PSI, Double Ram
- 2-1/16” x 4-1/16” 10,000 PSI Choke Manifold
- (1) 7 Station Accumulator Skid

NDS® OFFERINGS
- ROCKit (Oscillator)
- REVit Z Torque (Stickslip Mitigation)

NOV® OFFERINGS
- NOVOS Capable

TUBULARS
- Available at Operator’s Request

INDEPENDENCE® CONTRACT DRILLING

20475 SH 249, Suite 300, Houston, Texas 77070 | Main: 281-598-1230 | salesmanager@icdrilling.com | www.icdrilling.com