INDEPENDENCE 327

MAST
- Hydraulically Raised - Telescoping
- 142' Height
- 750,000 lbs. Static Hook Load

SUBSTRUCTURE
- Hydraulically Cable Raised - Cantilever Style
- 25' Floor Height (RKB)
- 22'-6" Clear Height (RBC)
- 27-1/2" Rotary Table
- Setback Capacity: 650,000 lbs.
- Racking Capacity: 26,000' (5.5" DP)

WALKING SYSTEM
- Hydraulic, Remote-Controlled Stompers
- 200' (X)
- 35' (Y)
- Integrated Cable Management System
- Custom Engineered Flowline

DRAWWORKS
- 1,500 HP Dual Speed - American Block®
- (1) 1,500 HP AC Motor

TRAVELING BLOCK ASSEMBLY
- 500 Ton Canrig® 1250 AC Top Drive
- 51,400 ft-lbs. Torque @ 118 RPM
- 500 Ton Traveling Block

PIPE HANDLING EQUIPMENT
- Forum® FR120 Iron Roughneck
- Forum® Pipe Wrangler

ENGINE PACKAGE
- (4) CAT® 3512C Diesel Engines
- (4) 1750 kVa Generator Sets
- Bi-Fuel Equipped

CONTROL SYSTEM
- IEC® VFD House
- Drillers Cabin w/IEC® Controls
- VFD Interlock Relay for High Line Capacity

MUD PUMPS
- (3) 1,600 HP Triplex - 7,500 PSI
- (3) 1,500 HP AC Motor

MUD SYSTEM
- 1000 BBL. Pit Capacity - 7,500 PSI
- (3) Derrick® Hyperpool Shale Shakers
- MGS 600 GPM 48" D / 16' L

MUD MIXING EQUIPMENT
- (2) Chemical Mixing Hoppers
- Caustic Barrel

LIQUID STORAGE
- 450 BBL. Water Storage Tank
- 400 BBL. Diesel Storage Tank

BOP EQUIPMENT
- Trolly Beam Handling System
- (2) Pneumatic Winches
- 13-5/8" x 5,000 PSI, Annular
- 13-5/8" x 10,000 PSI, Single Ram
- 13-5/8" x 10,000 PSI, Double Ram
- 2-1/16" x 4-1/16" 10,000 PSI Choke Manifold
- (1) 7 Station Accumulator Skid

NDS® OFFERINGS
- ROCKit (Oscillator)
- REVit Z Torque (Stickslip Mitigation)
- SmartDRILL (Automated Connection Sequencing)
- SmartNAV (Directional Guidance)
- SmartPLAN (Drilling Roadmap)
- SmartSLIDE (Automated Directional)

TUBULARS
- Available at Operator's Request

INDEPENDENCE® CONTRACT DRILLING

20475 SH 249, Suite 300, Houston, Texas 77070 | Main: 281-598-1230 | salesmanager@icdrilling.com | www.icdrilling.com